

## Dri-Box® Adapters with Non-Metallic Cover and Base

This adapter will accept any wiring device and standard size wall plate. Clear is not paintable, white is textured and paintable. UV rated plastic for long outdoor life.

CATALOG NUMBER	UPC/DCI/NAED MFG #018997	ORIENTATION/COVER COLOR	UNIT PKG	STD PKG	DIM A	DIM B	DIM C
DBPV1*	17852	Vertical/White	1	4	6.313	3.078	2.954
DBPV1C*	17840	Vertical/Clear	1	4	6.313	3.078	2.954
DBPH1*	17853	Horizontal/White	1	4	4.000	5.685	2.940
DBPH1C*	17845	Horizontal/Clear	1	4	4.000	5.685	2.940
DBP2	17855	Vertical/White	1	4	6.313	5.250	2.940
DBP2C	17857	Vertical/Clear	1	4	6.313	5.250	2.940
DBP21D	17849	Vertical/White	1	4	6.313	5.250	4.175
DBP21DC	17848	Vertical/Clear	1	4	6.313	5.250	4.175



PATENTED.

**Note: Meets NEC section 406.9 (B) for the protection of exterior outlets where an extra duty weatherproof in use cover is required for 15 or 20 AMP receptacles installed outdoors.** \*Includes (1) standard duplex and (1) GFCI face plate.



**DBPV1/DBPV1C:**  
Vertical Mount, Single Gang

**DBPH1/DBPH1C:**  
Horizontal Mount, Single Gang

**DBP2/DBP2C/DBP21D/DBP21DC:**  
Vertical Mount, Two Gang




DBPV1C



### INSTALLATION INSTRUCTIONS

Remove the cover by expanding ear tabs over the pivot pins. To replace the cover, simply snap over the pivot pins. **NOTE:** It is not required to remove the cover for installation.



Arlington's DRI-BOX® Adapter comes with both standard duplex and GFCI plates for added convenience, but works with any standard non-metallic or metal wall plate. Our DRI-BOX® meets OSHA lockout/tagout requirements using a standard padlock.

